BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT42445

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/02/2020-21, Date: 28.05.2020

Name of Work:Maintenance of Storm Water Drains in Ward No.8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHALINI SAMPANGI	
				In Figures	In Words
1	35.71	KSRRB M200-15.2. Dismantling of existing structures like culverts, Bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceble material and stacking the serviceble material with all lifts complete as per specifications. iii) Dismantling Stone Masonry B. Rubble Stone maonry in cement mortar (P.No.140, I.No.18.27 of PW,P&IWTD SR 2018-19)	Cum	350.11	Rupees Three Hundred Fifty and Eleven Paise Only
2	20.7	KSRRB M200-12.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. MORTH Specification No. 202. (P.No. 139, I.No. 18.18 of CSR 2018-19)	Cum	658.15	Rupees Six Hundred Fifty Eight and Fifteen Paise Only
3	414	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.143, I.No.19.1 of PW, P&IWTD SR 2018-19)	Cum	231.49	Rupees Two Hundred Thirty One and Forty Nine Paise Only
4	35.71	KSRB 5.2-3: Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as per specifications. Specifcation No. KBS 5.1.13.(using available stones) (P.No.25, I.No.5.6 of PW, P&IWTD S.R 2018-19)	Cum	2988.79	Rupees Two Thousand Nine Hundred Eighty Eight and Seventy Nine Paise Only
5	11.9	KSRB 5.2-3: Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as per specifications. Specifcation No. KBS 5.1.13. (P.No.25, I.No.5.6 of PW, P&IWTD S.R 2018-19)	Cum	4584.33	Rupees Four Thousand Five Hundred Eighty Four and Thirty Three Paise Only
6	105.8	KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.No.115, I.No.15.1 of PW, P&IWTD S.R 2018-19)	Sqm	140.64	Rupees One Hundred Forty and Sixty Four Paise Only
7	20.7	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No.4.6 of PW,P&IWTD S.R 2018-19)	Cum	5408.23	Rupees Five Thousand Four Hundred Eight and Twenty Three Paise Only

Shalini S

Signature of the Contractor

27/07

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

27/07